

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-20351-00-00
Spot: SWSENESW Sec/Twnshp/Rge: 2-24S-36W
1518 feet from S Section Line, 3073 feet from E Section Line
Lease Name: BARRICKLOW Well #: 1-2
County: KEARNY Total Vertical Depth: 3002 feet

Operator License No.: 32864
Op Name: XTO ENERGY INC.
Address: 210 PARK AVE STE 2350
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2695		WITH 10 SX CMT
SURF	8.625	526		WITH 300 SX CMT
PROD	4.5	3000	888	WITH 700 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/12/2012 1:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: ART Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: DUMP 10 SX CMT ON CIBP @ 2695', FILL HOLE WITH 9 PPG MUD, PUMP A 100' CMT PLUG ACROSS ANHYDRITE FROM 1850' - 1950'. CUT & PULL CASING @ FREEPOINT (TOC +/- 1150'), PUMP A 100' CMT PLUG 50' BELOW TO 50' ABOVE CSG STUB. PUMP A 300' CMT PLUG 470' - 770' TO COVER BASE OF TREATABLE WATER & SURF CSG SHOE. PUMP A CMT PLUG FROM 4' - 34' BELOW GROUND LEVEL. WELD ON ID PLATE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL
Date/Time Plugging Completed: 03/13/2012 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2695' SET PREVIOUSLY. SPOT 10 SX CMT ON TOP OF PLUG VIA TBG. 1ST PLUG PUMP 30 SX CMT W/100# HULLS AT 1950' THROUGH TBG. CIRCULATED. SHOOT 4 1/2" CASING OFF AT 888' & TOO. TAG TOC @ 1748'. 2ND PLUG AT 888' WITH 50 SX CMT. 3RD PLUG AT 800' WITH 100 SX CMT. 4TH PLUG AT 60' TO 0' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
2750	2866		COUNCIL GROVE

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through:

District: 01

Signed



(TECHNICIAN)

RECEIVED
MAR 13 2012
KCC DODGE CITY

RECEIVED
MAR 26 2012
KCC WICHITA

Form CP-275

3/27/12