

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22631-00-00
Spot: SESWNE Sec/Twnshp/Rge: 16-7S-19W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: MCCAULEY Well #: 5
County: ROOKS Total Vertical Depth: 3440 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	253		180 SX
PROD	4.5	3425		475 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/14/2012 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DALE FERLAND Company: BACH OIL Phone: (785) 302-1435

Proposed Plugging Method: Ordered 350sx 60/40 pozmix 4% gel cement and 500# hulls
DV tool @1348' w/350sx

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/14/2012 4:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1458', pumped 250sx cmt w/500# hulls to circulate to surface.
PTOH. Hooked to 4 1/2" casing and pumped 15sx cmt. SIP 325psi

Perfs:

Top	Bot	Thru	Comments
3389	3392		ARBUCKLE
3306	3306		LKC
3284	3284		LKC
3262	3262		LKC
3212	3214		LKC

Remarks: ALLIED #42420

Plugged through: TBG

RECEIVED

MAR 26 2012

KCC WICHITA

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

MAR 20 2012

Form CP-2/3

✓ 3/27/12