

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00439-00-01
Spot: NWNESENE Sec/Twnshp/Rge: 28-14S-17W
3651 feet from S Section Line, 411 feet from E Section Line
Lease Name: DINKLE OWWO Well #: 2
County: ELLIS Total Vertical Depth: 3488 feet

Operator License No.: 31021
Op Name: CASTELLI EXPLORATION, INC.
Address: 6908 W 112TH
OKLAHOMA CITY, OK 73162

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	225		0 SX
PROD	5.5	3485		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/20/2012 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: RICK POPP Company: CASTELLI EXPLORATION INC. Phone: (620) 786-5508

Proposed Plugging Method: Ordered-315sacks 60/40 poz mix 4% gel; 500 # hulls; 11 sacks gel.
Perf Tech shot 2 hole perforations @ 1650'; 1116'; 580'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/20/2012 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 3370, Quality rigged to tubing & mixed & pumped 11 sacks gel followed by 75 sacks 60/40 poz 4 % gel with 300 # hulls mixed in.
Pulled tubing to 1650', Quality rigged to tubing & pumped 150 sacks 60/40 poz with 200 # hulls mixed into circulate cement to surface.
Pulled tubing topped off 5.5" CSG with 20 sacks .Hole standing Full.
Rigged to 8.625" CSG pumped 5 sacks backside was standing full of cement.

Perfs:

Top	Bot	Thru	Comments
3485	3488		ARBUCKLE
3250	3302		LKC
3200	3204		TOR
3130	3133		TOP

Remarks: QUALITY OIL WELL CEMENTING CO. TICKET # 478

Plugged through: TBG

RECEIVED

MAR 26 2012

KCC WICHITA

District: 04

Signed _____

(TECHNICIAN)

MAR 21 2012

Form CP-2/3

✓ 3/27/12