

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-00909-00-01
Spot: NWSENWSW Sec/Twnshp/Rge: 28-10S-17W
1800 feet from S Section Line, 700 feet from W Section Line
Lease Name: GANOUNG Well #: A 2
County: ROOKS Total Vertical Depth: 2175 feet

Operator License No.: 8925
Op Name: LIBERTY OPER & COMPL, INC
Address: 308 W MILL
PLAINVILLE, KS 67663

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 03/19/2012 9:00 PM
Plug Co. License No.: 34481 Plug Co. Name: TORNADO DRILLING COMPANY, LLC
Proposal Rcvd. from: TONY RICHARDSON Company: TORNADO DRILLING COMPANY Phone: (785) 662-8000

Proposed Plugging Method: LOST HOLE AT 2175', DECIDED TO P/A. ORDERED OUT 205 SX 60/40 POZ MIX 4% GEL, & 1/4# FLOSEAL PER/SX.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: PARTIAL
Date/Time Plugging Completed: 03/20/2012 4:40 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

RAN DRILL PIPE TO BOTTOM AND PUMPED 60 BBL HEAVY DRILLING MUD, PULLED TO 1375' ALLIED PUMPED 25 SX CEMENT, PULLED TO 850' AND PUMPED 100 SX CEMENT, PULLED TO 265' AND PUMPED 40 SX, PULLED TO 40' 10SX W/ WIPER PLUG. PLUGGED RAT HOLE W/ 30 SX. JOB COMPLETED AT 4:40 AM.

Remarks: WITNESS ANHY & DAKOTA PLUG ONLY.

Plugged through: DP

RECEIVED
MAR 26 2012
KCC WICHITA

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

MAR 23 2012

Form CP-2/3

3/27/12