

TO: STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-073-22209-00-00
Spot: NWSWNWNW Sec/Twnshp/Rge: 4-23S-11E
750 feet from N Section Line, 310 feet from W Section Line
Lease Name: RICKABAUGH Well #: 6
County: GREENWOOD Total Vertical Depth: 1993 feet

Operator License No.: 6112
Op Name: LONG DRILLING COMPANY, LLC
Address: PO BOX 131
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	5.625	103		50 SX
PROD	4.5	1992		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/23/2012 2:00 PM
Plug Co. License No.: 6112 Plug Co. Name: LONG DRILLING COMPANY, LLC
Proposal Rcvd. from: TOM LONG Company: _____ Phone: (620) 678-3461

Proposed Plugging Method: 50' cement plug @ 1980' 50' cement plug @680' 150' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 02/23/2012 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

spot 5 sxs cement w/ dump baler @ 1980', ran tubing to 680' pumped 50 sxs cement, pulled tubing to 150' pumped 70 sxs cement to surface. Inside & outside of casing, gel spacers between cement plugs

RECEIVED

MAR 19 2012 MH

KCC Chanute Dist. #3

Remarks: WELL WAS FLOWING EMERGENCY PLUGGING ORDERS GIVEN BY MIKE HEFFERN, STEVE KORF

Plugged through: TBG

District: 03

Signed

Mike Heffern
(TECHNICIAN)

RECEIVED

MAR 26 2012

Form CP-2/3

3/27/12

KCC WICHITA