

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-20667-00-00
Spot: SENENE Sec/Twnshp/Rge: 27-32S-15W
4088 feet from S Section Line, 5089 feet from W Section Line
Lease Name: MILLS Well #: R-1
County: BARBER Total Vertical Depth: 1869 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2600		WITH 2 SX CMT
SURF	8.625	300		WITH 250 SX CMT
PROD	5.5	3592	980	

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/08/2012 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: ART SCHOENHOFER Company: RAYMOND OIL Phone: (316) 267-4214

Proposed Plugging Method: SAND THE BOTTOM TO 3450' WITH 5 SX CMT. SET A CIBP @ 2600' WITH 2 SX CMT. PLUG AT 780' WITH 15 SX GEL & 50 SX CMT. PLUG AT 320' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: PARTIAL
Date/Time Plugging Completed: 03/08/2012 11:10 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

SANDED THE BOTTOM TO 3450' WITH 5 SX CMT. SET A CIBP @ 2600' WITH 2 SX CMT. 1ST PLUG AT 784' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 38' WITH 15 SX CMT. CMT CIRCULATED.

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
MAR 13 2012
KCC DODGE CITY

RECEIVED
MAR 26 2012
KCC WICHITA
3/29/12