

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21699-00-00
Spot: W2NWNENE Sec/Twnshp/Rge: 6-13S-31W
330 feet from N Section Line, 1250 feet from E Section Line
Lease Name: HULLET Well #: 2-6
County: GOVE Total Vertical Depth: 4715 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	292		180 SX
T1	2.375	4597		
PC		2236		220 SX
PROD	4.5	4692		185 SX

Well Type: ON DAM UIC Docket No: _____ Date/Time to Plug: 03/05/2012 8:30 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: TIM GILLOGLY Company: LARIO Phone: (620) 805-1300

Proposed Plugging Method: Ordered 400sx 60/40 4% gel cement and 300# hulls. PC @2237'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/05/2012 12:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 3410'. Pumped 150sx cmt w/75# hulls.
Pulled tubing to 2222'. Pumped 75sx cmt w/75# hulls.
Pulled tubing to 1095'. Pumped 85sx w/50# hulls. Cement circulated.
PTOH. Connected to 4 1/2 casing and pumped 15sx cmt.
Connected to 8 5/8 surface casing. Pumped 5sx cmt. 300 psi MAX.

Perfs:

Top	Bot	Thru	Comments
4598	4606		

Remarks: CONSOLIDATED TICKET #33928

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

RECEIVED

MAR 26 2012

KCC WICHITA

MAR 12 2012

Form CP-2/3

3/29/12