

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21293-00-00
Spot: NESWSE Sec/Twnshp/Rge: 31-9S-17W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: GANOUNG Well #: 4
County: ROOKS Total Vertical Depth: 3640 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3485		
SURF	8.625	160		
SURF	8.625	164		70 SX
PROD	4.5	3639		625 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/21/2012 12:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: DV @ 1396' W/425SX, C.I.B.P. @ 3485' PRODUCTION PERFORATIONS 3317-3484. CASING LEAKS FROM 2000'-2636'. ORDERED OUT 300SX 60/40 POZ-MIX 4%GEL W/ 500# HULLS.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/21/2012 4:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

RAN TUBING TO 2970', SWIFT SERVICES PUMPED 90 SX CEMENT W/225# HULLS, PULLED TUBING TO 1980' & PUMPED 75SX CEMENT W/150# HULLS, CIRCULATED CEMENT. P.T.O.H. SQZ'D 25SX CEMENT 700# MAX, AND 200# S.I.P. BACKSIDE FULL OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3549	3552		
3539	3543		
3525	3529		
3480	3484		
3458	3460		
3440	3444		
3317	3320		

Remarks: TICKET # 21327

Plugged through: TBG

RECEIVED
MAR 26 2012
KCC WICHITA

District: 04

Signed



(TECHNICIAN)

CM

MAR 23 2012

Form CP-2/3

✓ 3/29/12