

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20169-00-01
Spot: NENWSW Sec/Twnshp/Rge: 27-29S-17W
2970 feet from N Section Line, 990 feet from W Section Line
Lease Name: JANTZ OWWO Well #: 1-27
County: KIOWA Total Vertical Depth: 4891 feet

Operator License No.: 31925
Op Name: QUALITY WELL SERVICE, INC.
Address: 190 US HWY 56
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	468		WITH 300 SX CMT
PROD	5.5	4889	2100	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/15/2012 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4770' & 5 SX CMT. PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 490' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 03/15/2012 5:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

SANDED TO 4770' & SPOTTED 5 SX CMT ON TOP. 1ST PLUG AT 1000' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 490' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

RECEIVED
MAR 28 2012
KCC WICHITA

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
MAR 21 2012
KCC DODGE CITY

Form CP-2/3

3/29/12

RAWZ