

15-135-19071-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NESS County. Sec. 19 Twp. 16S Rge. (E25) (W)

Location as "NE/CNW/SW" or footage from lines C NE NE

Lease Owner PICKRELL DRILLING COMPANY

Lease Name HORACEK Well No. 1

Office Address 705 4th NATL BANK BLDG, WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed March 4, 1963 19__

Application for plugging filed March 4, 1963

Application for plugging approved March 4, 1963


Plugging commenced March 4, 1963

Plugging completed March 4, 1963

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert P. Leiker

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4605 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	264'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 240'. Set plug. Cemented with

20 sacks cement. Heavy mud to 40'. Set plug.

Cemented with 10 sacks cement to bottom of

cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 14 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PICKRELL DRILLING COMPANY

Address 705 4th NATL BANK BLDG, WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

C. W. SEBITS (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. SEBITS

705 4th NATL BANK BLDG, WICHITA, KANSAS

(Address)

SUBSCRIBED AND SWORN to before me this 11th day of MARCH, 1963

My commission expires June 21, 1966

Maxine Blackman
Maxine Blackman Notary Public.



ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th National Bk Bldg
Wichita, Kansas
LOCATION: HORACEK NO. 1, C NE NE 19-16S-25W
Ness County, Kansas

Rotary Drilling Commenced 2-18-63

Rotary Drilling Completed 3--4-63

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (7 jts) 8 5/8" Surface Casing set at 264', cemented with 180 sacks cement. Circulated. Completed 3:00 P.M. February 19, 1963. No oil string run, dry and abandoned.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

100	Top Soil and Sand	<u>C. F. S.</u>
880	Shale and Shells	4405
960	Sand	4522
1215	Shale and Shells	4532
1380	Red Beds	4537
1393	Blaine	4542
1420	Shale and Shells	4547
1740	Red Bed	4552
1975	Shale and Shells	4557
2015	Anhydrite	4562
2220	Shale and Shells	4572
2420	Shale and Lime Shells	4580
2852	Lime and Shale	4590
3035	Lime	4605
3185	Lime and Shale	
3385	Lime	<u>Slope Tests</u>
3585	Lime and Shale	3803
3668	Lime and Sandy Shale	4014
3815	Lime and Shale	4427
4305	Lime	
4430	Lime and Shale	
4455	Fort Scott Lime	<u>S. L. M.</u>
4499	Lime	3799
4529	Conglomerate	4201
4537	Mississippian Dolomite	4476
4605	Mississippian - RTD	

MAR 14 1963

CONSERVATION DIVISION
Wichita, Kansas


The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 11th day of March, 19 63, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.



My commission expires: June 21, 1966

[Signature]
Maxine Blackman Notary Public