

STATE OF KANSAS
STATE CORPORATION COMMISSION
206 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-22520-00-00

LEASE NAME Horacek

WELL NUMBER 1

SPOT LOCATION SE SE NE

SEC. 19 TWP. 16 RGE. 25 (E) or (W)

COUNTY Ness

Date Well Completed 4-17-84

Plugging Commenced 4-17-84

Plugging Completed 4-17-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Viking Resources

ADDRESS 217 E. William Wichita, Ks. 67202

PHONE # (316) 262-2502 OPERATORS LICENSE NO. 5011

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 1

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation N/A Depth to top _____ bottom _____ T.D. 4558'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	286'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Fill hole w/mud.

Spotted 50 sx. cement @ 1980' thru drill pipe.

Spotted 50 sx. cement @ 900' thru drill pipe.

Spotted 50 sx. cement @ 330' thru drill pipe.

Set bridge plug @ 40', Spotted 10 sx. cement thru drill pipe.

Spotted 15 sx. cement in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address 401 East Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, **RECEIVED** Ernest Sifford God.

STATE CORPORATION COMMISSION

(Signature) Ernest Sifford


(Address) 401 E. Douglas, Suite 500 Wichita, Ks. 67202

APR 27 1984


Subscribed and sworn to before me this 26th day of April, 1984

CONSERVATION DIVISION
Wichita, Kansas

My Commission expires:



David F. Jamis
David F. Jamis, Notary Public



15-135-22520-00-00

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Viking Resources, Inc. 217 E. William Wichita, Ks. 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
Wichita, Ks. 67202

Lease Name Horacek Well No. 1

Sec. 19 T. 16S R. 25W Spot SE SE NE

County Ness State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 286 with 200 sx. 2%gel
3%cc

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4558'

Drilling Commenced 4-8-84 Drilling Completed 4-17-84

Formation	From	To	Tops
Cellar	0	7	Anhydrite 1978
Shale, Sand	7	1150	
Sand, Shale	1150	1978	
Shale	1978	2380	
Lime, Shale	2380	3173	
Lime	3173	3330	
Lime, Shale	3330	4331	
Lime	4331	4558	

RECEIVED
STATE CORPORATION COMMISSION

APR 27 1984

CONSERVATION DIVISION
Wichita, Kansas