

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County. Sec. 19 Twp. 16S Rge. 25W E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines
S/2 SE SE


Lease Owner Dean Allison
Lease Name Pickering Well No. #1
Office Address 507 Insurance Building, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole

Date Well completed September 9, 1980 19
Application for plugging filed September 9, 1980 19
Application for plugging approved September 9, 1980 19
Plugging commenced September 9, 1980 19
Plugging completed September 9, 1980 19
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation Depth to top Bottom Total Depth of Well 4545'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole plugged with 50-50 pozmix, 6% gel, as follows:
70 sacks @ 1170', 25 sacks @ 270', hulls and 10 sacks @ 40', 3 sacks in rathold, 2 sacks in mousehole. Plugging completed 11:15 p.m., September 9, 1980.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1980
7-19-80

CONSERVATION DIVISION
WICHITA, KANSAS

STATE OF KANSAS COUNTY OF BARTON
Charles W. Steincamp (employee of owner) or owner/operator
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of September, 1980.

Loneita Barry
Loneita Barry Notary Public.

My commission expires 3-28-84.



DRILLERS LOG

#1 Pickering

CASING RECORD: 7 jts. new 20# 8-5/8" surface casing
 COMPANY: Dean Allison
 DESCRIPTION: S/2 SE SE Section 19-16S-25W Ness County, Kansas
 CONTRACTOR: Strata Drilling Company
 COMMENCED: September 3, 1980
 ELEVATION: 2586' KB
 TOTAL ROTARY DEPTH: 4545'
 COMPLETED: September 9, 1980

D & A

FORMATION	FROM	TO	REMARKS
Surface soil, shale	0	293	Ran 282' new 20# 8-5/8" surface casing; set and cemented at 287' with 180 sacks common cement, 2% gel, 3% C.C. Cement circulated. Plug down at 8:00 p.m., September 3, 1980.
Shale, sand, shale	293	1953	
Anhydrite	1953	1988	
Shale	1988	2375	
Lime and shale	2375	4250	
Lime	4250	4330	
Lime and shale	4330	4545	
			Ran 3 drill stem tests.
			Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks at 1170', 25 sacks at 270', hulls and 10 sacks at 40', 3 sacks in rathole, 2 sacks in mousehole. Plugging completed at 11:15 p.m., September 9, 1980.

STATE OF KANSAS)
) ss
 COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Charles W. Steunoy

Sworn to and subscribed before me this 11th day of September, 1980.

My appointment expires 3-28-84.

Loneita Barry
 Loneita Barry, Notary Public

