


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

Ness County, Sec. 19 Twp. 16S Rge. (E) 25 (W)  
Location as "NE/CNW&SW&" or footage from lines C S/2 SW SE  
Lease Owner Palomino Petroleum  
Lease Name Pickering Well No. 1  
Office Address 304 Insurance Bldg., Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 23 19 76  
Application for plugging filed March 23 19 76  
Application for plugging approved March 23 19 76  
Plugging commenced March 23 19 76  
Plugging completed March 23 19 76  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4538 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	261'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged as follows: Plugged at 720' with 70 sacks of 50-50 pozmix; plugged at 250' with 20 sacks of 50-50 pozmix; plugged at 40' with 10 sacks of 50-50 pozmix. Plug down 11:30 P. M. March 23, 1976.

RECEIVED  
DATE 4-1-76  
APPROVED


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Strata Drilling Company  
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Kenneth J. Link (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link  
Kenneth J. Link, President  
P. O. Box 355, Great Bend, Kansas 67530  
(Address)

Subscribed and sworn to before me this 24th day of March, 19 76  
December 14, 1977

Elaine H. Taylor  
Notary Public.



D R I L L E R S      L O G

#1 Pickering

CASING RECORD:  
256' of used 8-5/8"  
surface casing.

COMPANY: Palomino Petroleum  
CONTRACTOR: Strata Drilling Company  
COMMENCED: March 15, 1976  
COMPLETED: March 23, 1976

DESCRIPTION: C S/2 SW SE  
Section 19-16S-25W  
Ness County, Kansas  
ELEVATION: 2583' KB

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	280	Ran 256' of used 8-5/8" surface casing; set and cemented at 261' with 175 sacks of common cement, 2% gel and 3% C. C. Plug down at 11:00 P. M. March 15, 1976.
Shale & Sand	280	1750	
Shale w/Sand Streaks	1750	2200	
Shale & Lime	2200	4538	

ROTARY TOTAL DEPTH: 4538'

Ran four Drill Stem Tests.

No electric log.

D. & A.

Hole plugged as follows: Plugged at 720' with 70 sacks of 50-50 pozmix; plugged at 250' with 20 sacks of 50-50 pozmix; plugged at 40' with 10 sacks of 50-50 pozmix. Plug down at 11:30 P. M. March 23, 1976.

RECEIVED  
STATE OF KANSAS COMMISSION

APR 01 1976  
4-1-76  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

*Kenneth J. Link*  
Kenneth J. Link, President

Subscribed and sworn to before me this 24th day of March, 1976.

My Commission Expires:

December 14, 1977

*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public

