

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135,21,329-00-00

LEASE NAME Michaelis

WELL NUMBER "B" #5

2970 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 20 TWP. 16 RGE. 25 (E) or (W)

COUNTY Ness

Date Well Completed \_\_\_\_\_

Plugging Commenced 4-30-91

Plugging Completed 5-6-91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Petroleum Inc.

ADDRESS Box 186, Plainville, Ks. 67663

PHONE# (913) 434-4647 OPERATORS LICENSE NO. 5238

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 24, 1991 (date)

by Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4547'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	235'	None
				5-1/2"	4522'	1,735.13'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Dumped sand to 4470' and 5 sacks cement. Shot casing at 3833', 3306', 2911', 2539' & 1129'. Pulled 43 joints of 5-1/2" casing. Halliburton plugged well with 10 sacks gel and 50 sacks cement spotted through the casing at 2000' and 80 sacks cement at 1086', 50 sacks cement at 350' and 10 sacks 60/40 pozmix cement with 6% gel to fill to surface.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

RECEIVED

STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 1th day of May, 1991

MAY 8 1991

CONSERVATION DIVISION My Commission Expires \_\_\_\_\_  
Wichita, Kansas

STATE NOTARY PUBLIC  
KANSAS  
IONA M. LEATHERMAN  
Barton County, Kansas  
My Appt. Exp. 4-26-91

Iona M. Leatherman  
Notary Public