

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

RECEIVED

FEB 28 1975

WELL PLUGGING RECORD

WICHITA  
PROD. DEPT.

Location as "NE/CNWKSW" or footage from lines 150' West of N/2 SW SE  
County, Sec. 20 Twp. 16 Rge. 25 (E) W (W)  
Lease Owner Petroleum, Inc.  
Lease Name Michaelis 'B' No.3 Well No. 3  
Office Address 800 R. H. Garvey Bldg. 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 21 1975  
Application for plugging filed February 21 1975  
Application for plugging approved February 21 1975  
Plugging commenced Plugged February 21 1975  
Plugging completed Feb. 21 1975  
Reason for abandonment of well or producing formation Dry Hole


Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 454.6 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	surf. casing	0	328'	8-5/8	Yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st plug @ 800' with 70 sacks  
2nd plug @ 240' with 20 sacks  
Top plug @ 40' with 10 sacks Poz

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 4 1975  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor SLAWSON DRILLING COMPANY, 408 One Twenty Building Wichita 67202  
Address \_\_\_\_\_

STATE OF KANSAS COUNTY OF SEDGWICK No. \_\_\_\_\_  
James C. Remsberg, Petroleum Engineer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg  
408 One Twenty Building (Address)

Subscribed and sworn to before me this 27th day of February, 1975

Mary Lou Taylor  
Notary Public.



## DRILLERS LOG

COMPANY: Petroleum, Inc.  
800 R. H. Garvey Building  
Wichita, Kansas 67202

LEASE: Michaelis 'B' No.3  
150' West of N/2 SW SE  
Sec. 20-16S-25W  
Ness County, Kansas

CONTRACTOR: SLAWSON DRILLING COMPANY, INC.  
408 One Twenty Building  
Wichita, Kansas 67202

TOTAL DEPTH: 4546'

COMMENCED: February 11, 1975

COMPLETED: February 21, 1975

CASING: Set 8-5/8" at 328' with 225 sacks

0 to 335'	12½" surface hole
335' to 730'	Shale
730' to 1445'	Shale & Sand
1445' to 1690'	Sand
1690' to 1710'	Shale
1710' to 1947'	Shale & Shells
1947' to 1983'	Anhydrite
1983' to 2555'	Shale & Shells
2555' to 2805'	Shale & Lm
2805' to 3895'	Lime & Shale
3895' to 4085'	Shale - Shells
4085' to 4433'	Lime
4433'	Ft. Scott
4433' to 4515'	Lime
4515' to 4546'	Miss
4546'	RTD

RECEIVED  
STATE CORPORATION COMMISSION

MAR 4 1975

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS  
COUNTY OF SEDGWICK

I, JAMES C. REMSBERG, of the SLAWSON DRILLING COMPANY, INC.  
upon oath state that the above and foregoing is a true and correct copy of  
the log of the Michaelis 'B' No.1.

*James C. Remsberg*

Subscribed and sworn to me on February 27, 1975.

My commission expires 1-17-77

*Mary Lou Taylor*

