

15-101-20042-00-00

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
Wichita, Kansas 67217

P. O. Box 17027

Lane _____ County, Sec. 36 Twp. 18S Rge. (E) 27 (W)

Location as "NE/CNW/SW" or footage from lines c SE SE

Lease Owner John Eaton

Lease Name Shramek Well No. 1

Office Address Shields, Kansas 67874

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 3, 19 72

Application for plugging filed November 3, 19 72

Application for plugging approved November 3, 19 72

Plugging commenced November 3, 19 72

Plugging completed November 3, 19 72

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4600 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	251'	8 5/8"	251'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug:

750' w/110 sacks cement

275' w/ 30 sacks cement

40' w/ 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
NOV 9 1972
CONSERVATION DIVISION
Wichita, Kansas
11-09-1972

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hellar Drilling Company, Inc.

Address 339 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.

D. L. Hellar, President of Hellar Drlg. Co, Inc (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) D. L. Hellar D. L. Hellar, President
339 Union Center Bldg., Wichita, Kansas 67202

(Address)

SUBSCRIBED AND SWORN to before me this 8th day of November, 19 72

My commission expires March 25, 1976.

Catherine Darcey
Catherine Darcey - Notary Public.



15-101-20042-00-00

DRILLER'S LOG

COMPANY: John Eaton, Shields, Kansas 67874
 CONTRACTOR: Hellar Drilling Company, Inc., 339 Union Center Bldg., Wichita, Kansas 67202
 LEASE: #1 Shramek
 LOCATION: c SE SE 36-18S-27W, Lane County, Kansas
 COMMENCED: October 25, 1972
 COMPLETED: November 3, 1972
 CASING: Set 8 5/8" Surface Casing @ 251' w/175 sacks cement

0-253	Surface soil & lime
253-420	Shale
420-1343	Shale-Red Bed & Shells & Sand
1343-1355	Blaine Anhy.
1355-1775	Shale & Sand
1775-1945	Shale & Red Bed
1945-1980	Anhy.
1980-2290	Shale
2290-2488	Salt Section
2488-2663	Lime & Shale
2663-2870	Lime
2870-3567	Lime & Shale (Waub. & Topeka)
3567-3740	Lime & Shale (Topeka)
3740-3875	Lime
3875-4089	Lime (L.K.C.)
4089-4185	Lime
4185-4299	Lime (L.K.C.)
4299-4545	Lime
4545-4567	Cherokee & Miss.
4567-4600	Miss.
4600	Rotary Total Depth

D & A

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 9 1972
 11-09-1972
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Shramek, located in c SE SE 36-18S-27W, Lane County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 8th day of November, 1972.

Catherine Darcey
 Notary Public - Catherine Darcey

My Commission Expires:
 March 25, 1976.

