

15-101-00014-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Lane _____ County. Sec. 19 Twp. 18 Rge. 27 (E) W (W)

Location as "NE/CNW/SW" or footage from lines. NW NW NW

Lease Owner Trans Era Pet. Inc.

Lease Name Fenley Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10/25/52 19

Application for plugging filed 10/23/52 19

Application for plugging approved 10/23/52 19

Plugging commenced 10/24/52 19

Plugging completed 10/24/52 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4864 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	250	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Finished laying down drill pipe, filled hole with mud to 240', set first plug, 1/2 sack hulls and 20 sacks cement. Filled hole to 40', set second plug, 1/2 sack hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

Address _____

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

Hebert R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H.R. Michaelis

Russell, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 29th day of October, 1952

My commission expires 6-17-54.

Robert A. Samuel
STATE CORPORATION COMMISSION Notary Public.



PLUGGING 24-2675-S 2-52-20M
FILE SEC 197 18 R 274
BOOK PAGE 54 LINE 35

OCT 31 1952
10-31-1952
CONSERVATION DIVISION
Wichita, Kansas

15-101-00014-00-00

Trans Era Pet. Inc.
Fenley #1

NW NW NW 19-18-27W
Lane County, Kansas

Total Depth: 4864'
Comm. 10/1/52
Comp. 10/25/52

Casing

Cement

8 5/8" Set @ 250'

160 sacks Lehigh

Formation	Depth
Surface soil	15
Post Rock	65
Clay	100
Clay-sand	155
Sand-gravel	230
Shale-shell	280
Shale	570
shale-shells	710
Shale-sand	1000
Shale-shells-	1600
Sand	1850
Shale-shells	1940
Red bed-shale	2080
Shale-shells	2480
Shale-anhydrite	2525
Shale	2585
Shale-Lime	4000
Lime	4510
Lime-shale	4680
Lime	4864'

STATE OF KANSAS)
) SS
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Clara Betty

Subscribed and sworn to before me this 29th day of October, 1952.

Clara Sumner

Notary Public



My commission expires: 6-17-54.

PLUGGING
FILE SEC-19 7/18 R-2724
BOOK PAGE 57 LINE 35

OK
10-31-1952
CONSERV
Wichita, Kansas