

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,227-00-01

LEASE NAME Stanley "B"

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 17 TWP. 18S RGE. 27W (E) or (W)

LEASE OPERATOR Chief Drilling, Inc.

COUNTY Lane

ADDRESS 120 S. Market #300, Wichita, Kansas 67202

Date Well Completed 10-23-85

PHONE# (316) 262-3791 OPERATORS LICENSE NO. 5886

Plugging Commenced 9-17-93

Character of Well Oil

Plugging Completed 9-17-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-12-93 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? all info. mailed 10-23-85

Producing Formation Ft. Scott Depth to Top 4499 Bottom 4524 T.D. 4637

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	261	none
				4 1/2	4637	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Mix & pump 400# hulls, 40 sx 60/40 pozmix w/6% gel, followed w/2000' gel spacer then 100 sx 60/40 pozmix w/6% gel down casing. Pressure to 1200#. Shut well in. Mix & pump 30 sx cement down annulus. Shut in w/75#. Well plugged @ 11:15 a.m. 9-17-93.

Name of Plugging Contractor Chief Drilling, Inc. License No. 5886

Address 120 S. Market #300, Wichita, Kansas 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chief Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Douglas W. Thimesch, President (Employee of Operator) ~~xxxx Operator~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well, Kansas filed the the same are true and correct, so help me God.

(Signature) Douglas W. Thimesch

(Address) 120 S. Market, #300, Wichita, KS



AND SWORN TO before me this 21 day of September, 19 93

Betty M. Abbott
Notary Public

My Commission Expires: 1-22-95

USE ONLY ONE SIDE OF EACH FORM

RECEIVED
STATE CORPORATION COMMISSION
09-23-1993
SEP 23 1993
CONSERVATION DIVISION
WICHITA, KANSAS