

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,463

LEASE NAME Muchow (Stanley)

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4950 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 16 TWP. 18S RGE. 27W (X) or (W)

COUNTY Lane

LEASE OPERATOR Whitetail Crude, Inc

ADDRESS P O Box 544, Ness City, KS 67560-0544

PHONE# (785) 798-3641 OPERATORS LICENSE NO. 31627

Date Well Completed 5/11/88

Plugging Commenced 1/26/01

Plugging Completed 1/26/01

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/25/01 (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Cherokee Sand Depth to Top 4561 Bottom 4571 T.O. P.BTD 4605

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	5 1/2					0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each so Spotted 500# of hulls mixed into 60 sks of 60-40 6% gel at 4500' through 2 3/8" tubing on bottom. Pulled tubing to 2200' and pumped 160 sks to surface. Pulled tubing out and top off the 5 1/2 to surface with 15 sks. Tied onto the 8 5/8" and pumped 15 sks and pressured

RECEIVED
STATE CORPORATION COMMISSION

Name of Plugging Contractor Swift Service, Inc License No. FEB 14 2001

Address P O Box 466, Ness City, KS 67560

02-14-2001
CONSERVATION DIVISION
Wichita, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Whitetail Crude, Inc


STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, President Whitetail Crude, Inc (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike J. Fritzler

(Address) Mike J. Fritzler, President
P O Box 544, Ness City, KS 67560-0544

SUBSCRIBED AND SWORN TO before me this 8th day of February, 2001, X



Debra Kerr
Debra Kerr Notary Public

My Commission Expires 1/20/2001

USE ONLY ONE SIDE OF EACH FORM

Form CP-
Revised 05-7

OR