

1 060657

API NUMBER 15- 101-21,212 -00-00 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE SW , SEC. 29 , T 16 S, R 28 (W) EX

990 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4169

Lease Name Tillotson Well # 1-29

Operator: Roger L. Martin

County Lane 151.45

Name & Address P. O. Box 47610

Well Total Depth 4660 Mississippi feet

Wichita, KS 67201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 346

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Mallard Drilling Co., Inc. License Number 5651

Address 405 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 5:30 pm Day: 13 Month: September Year: 19 85

Plugging proposal received from Roger Martin

(company name) Mallard (phone) 316-263-8218
Elevation 2775 Est.

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2194-2224'

1st plug at the base of the anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 50 sx cement

3rd plug at the base of the Dakota with 50 sx cement

4th plug 30' out of the surface pipe with 50 sx cement
solid bridge

5th plug hulls - plug at 40' Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:30 pm Day: 13 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement, 2nd plug at 1340' with 50
sx cement, 3rd plug at 1000' with 50 sx cement, 4th plug at 400' with 50 sx cement,

5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx ce
ment. 7th plug to circulate rat hole with 15 sx cement, 8th plug to circulate mouse

hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form. Wichita, Kansas)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(operator did not) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE SEP 24 1985

INV. NO. 10240
9-13

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

267-2697
CARD MUST BE SIGNED

Starting Date: September 1, 1985
month day year

API Number 15- 101-21,212-00-00
NW SE SW Sec. 29, Twp. 16, S, Rge. 28
(location) East West

OPERATOR: License # KCC# 4169
Name ROGER L. MARTIN
Address PO Box 47610
City/State/Zip Wichita, KS 67201
Contact Person Roger L. Martin
Phone 316-682-0038

990' Ft North from Southeast Corner of Section
3630' Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # MALLARD DRILLING CO. KCC#5651
Name WICHITA, KS
City/State

Nearest lease or unit boundary line 990' feet.
County Lane
Lease Name Tillotson Well # 1-29
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
X Oil Swd Infield Mud Rotary
Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water 150' feet
Lowest usable water formation 1,100'
Depth to Bottom of usable water 1,100' feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 320 ft. feet
Conductor pipe if any required feet
Ground surface elevation estimated 2775' feet MSL
This Authorization Expires 2-15-86

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Projected Total Depth 4650' feet
Projected Formation at TD Mississippian/St. Louis
Expected Producing Formations Lansing-KC, Marmaton, Cherokee

Approved By [Signature] Title Operator
8-15-85
Production string will be cemented immediately.

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications

to: 8/14/85 Signature of Operator or Agent

Form C-1 4/84

Move 9-3-85 set 320' of 8 1/8"

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1985

CONSERVATION DIVISION
Wichita, Kansas