

1090327

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NW NW NE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,548 -00/00
SEC. 25 ; T 16 S, R 28 W/E
4950 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6889

Lease Name Demand Well # 25-22
County Lane LAWE 151.45
Well Total Depth 4660 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 361

Operator: Oxford Exploration Company
Name & Address 1550 Denver Club Building
Denver CO 80202

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Plains, Inc. License Number 4072

Address Box 347, Ness City, KS 67560

Company to plug at: Hour: 1:00 pm Day: 25 Month: April Year: 19 85

Plugging proposal received from Warren Martin

(company name) Oxford (phone) 308-692-3466

were: 4 1/2" at 4657' PBD 4616' Perfs at 4586-94'

1st plug sanded bottom to 4500' and dumped 4 sx cement on top of sand through bailer,
set 50 sx cement at 1509' - tagged top of plug at 1286'. Perforated 4 holes at 1280'
and block squeezed through a R-4 packer with 125 sx cement. Packer left in hole at
1255' with 10 sx cement on packer - 40 sx cement on top of casing at 770'. Set 40 sx

Plugging Proposal Received by Robert B. Tarbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 7:30 pm Day: 25 Month: April Year: 19 85

ACTUAL PLUGGING REPORT

at 407' and 10 sx at 40'.

RECEIVED
STATE CORPORATION COMMISSION

MAY 02 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton. Recovered casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If desired, observe this plugging.)

Signed Robert Tarbutton
(TECHNICIAN)

DATE 5-7-85

INV. NO. 8023