

To: 1 090489 10-17
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,565 -00-60
80' S of
S/2 NE NW, SEC. 20, T. 16 S, R. 28 W/EX
4210 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6569
Operator: Carmen Schmitt Inc.
Name &
Address P.O. Box 47
Great Bend, KS 67530

Lease Name Tillotson Well # 1
County Lane
Well Total Depth 4619 150.11 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 230

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____
Plugging Contractor Allied Cementing License Number _____
Address _____

Company to plug at: Hour: 12:30 p.m. Day: 17 Month: 10 Year: 1994

Plugging proposal received from Walt Dinkel
(company name) Allied Cementing (phone) 913-672-3452

were: 5 1/2" at 4613' w/195 sx cement, PBD 4568', Perfs at 4500-10, 4446-51, 3922-3925'
DV tool at 2168' w/452 sx 50/50 Pozmix 8% gel, circulated

1st plug pump 2 sx hulls, 25 sx cement, and gel to 1600', 3 sx hulls and fill with cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15 p.m. Day: 17 Month: 10 Year: 1994

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" casing with 25 sx cement, 2 sx hulls,
24 sx gel, 210 sx cement. Maximum pressure 100 psi and shut in 0 psi.
Backside was pressured to 500 psi.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.
(if additional description is necessary, use BACK of this form.)

~~It is the responsibility of the plugging contractor to observe this plugging.~~

INVOICED
Signed [Signature] (TECHNICIAN)

DATE 11-17-94

INV. NO. 41596
10-17 JAN 19 1995