

1 050572

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,199 -00-00
NW SE NE, SEC. 19, T 16 S, R 28 (W)X
3630 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Lease Name Tillotson Well # 1

Operator: A. Scott Ritchie

County Lane 149.28

Name & Address 125 N. Market, Suite 950

Well Total Depth 4593 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 273

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 9 Month: July Year: 19 85

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 401/2" into 4260' PBTD 4260' Perfss 3948 56'; 4149 4154'; 4174 4177' Elevation

1st plug sand back to 3900' with 4 sx cement

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 15 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30 pm Day: 9 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3900' and dumped 4 sx cement on top of sand through bailer. 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 70 sx cement, 15 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 400 psi and shut in 100 psi

JUN 11 1985

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1800' 4 1/2" casing
(If additional description is necessary, use BACK of this form.)

INVOICED

(I did / did not) observe this plugging.

DATE 7-17-85

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 8975