

1 050662

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION W/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,603-00-00

SW SE, SEC. 19, T. 16 S, R. 28 W/2

666 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Lease Name Tillotson Well # 2

Operator: A. Scott Ritchie

County Lane 149.01

Name & Address 125 N. Market

Well Total Depth 4585 feet

Ste 950

Conductor Pipe: Size _____ feet

Wichita KS 67202

Surface Casing: Size 8 5/8 feet 285'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pullers License Number 6050

Address Box 347 Chase Kansas 67524

Company to plug at: Hour: 9:00 am Day: 8 Month: November Year: 1985

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pullers (phone) 316-938-2457

work: To pump down the 4 1/2 casing with 25x hulls - 30 sx of cement - 10sx gel - 4 1/2" wiper plug - 140sx of cement. Pump 50sx of cement down 8 5/8" x 4 1/2" annulus. 4 1/2 casing set @ 4584 4 1/2" DV @ 2152 w 450 sack of cement PBD 4542.55

Perts 4101-4193 Plugging Proposal Received by Richard Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15 pm Day: 8 Month: November Year: 1985

ACTUAL PLUGGING REPORT Pumped down the 4 1/2" casing with 25x hulls

30 sx of cement - 10sx gel - 4 1/2" wiper plug - 140sx of cement. Pumped 10sx of cement down 8 5/8" x 4 1/2" annulus. Maximum pump pressure on 4 1/2" 1800 psi shut in pressure 1100 psi

Remarks: Allied pumped 60/40 pozmix 6% gel cement (if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED STATE CORPORATION COMMISSION

NOV 22 1985

NOV 14 1985

Signed Richard M. Lacey (TECHNICIAN)

DATE _____

INV. NO. 11152