

To: 1 071063 4-29  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-30311-00-00 252  
15-135-30311-00-00 Drill Completion Date 3/30/67  
W/2 SW SW, SEC. 23, T. 16 S, R. 25 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5088  
Operator: John J. Darrah Oil  
Name & Address 412 E. Douglas, Suite 1  
Wichita, KS 67202

660 feet from S section line  
4950 feet from E section line

Lease Name K.S.U. Well # 1  
County Ness  
Well Total Depth 4577 148.75 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 291

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor John J. Darrah License Number 5088  
Address 412 E. Douglas, Suite 1, Wichita, KS 67202

Company to plug at: Hour: 11:45 a.m. Day: 29 Month: 4 Year: 19 92

Plugging proposal received from Joe Foelgnen  
(company name) John J. Darrah (phone) 316-793-3625

were: 5 1/2" at 4576' w/150 sx cement, PBTD 4544', Perfs at 4421-4543'  
1st plug pump 50 sx cement to perfs with 20 sx cement,  
2nd plug tag bottom plug, run tubing and pump 165 sx cement to 0'.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:15 p.m. Day: 29 Month: 4 Year: 1992

ACTUAL PLUGGING REPORT 1st plug pumped 50 sx common cement to perfs with 20 sx gel,  
2nd plug tagged bottom plug at 4250'. Ran tubing to 1954' and pumped 165 sx cement to 0'.

NOTE; Well squeezed at 3840' w/150 sx cement. 400 sx lite cement on backside from surface-  
10/29/86.

Remarks: Used 60/40 Pozmix 8% gel by Allied. No casing recovery.  
(if additional description is necessary, use BACK of this form)

~~(do not check)~~ observe this plugging.

DATE 5-14-92

INV. NO. 35-237

4-29

JUL 08 1992

Signed Dan Goodrow  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 6 1992  
CONSERVATION DIVISION  
Wichita, Kansas