

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-21346-03-00

CNW.SW, Sec. 23, T16 S, R25 W14

R

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5023

Lease Name K.S.U. Well # 2

Operator: KANSAS PETROLEUM, INC  
Name & Address STE. 100, 200 E. FIRST  
WICHITA, KS 67202

County NESS

Well Total Depth 4549 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 303'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 14 Month: FEB. Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO DON COOL

(company name) KELSO (phone) 316-938-2457

were: 50/50 Pozmix, 4% gel - 3% CC - cast iron bridge plug set  
@ 4499 w/ 5 sq cmt - rec. 1800' of 5 1/2" - pump sequence  
of 3 sq hulls, 15 sq gel, 70 sq cmt. Then 15 sq gel,  
1 sq hulls, release 8 5/8 plug and follow w/ 100  
sq cmt.

orders by S. Durrant

Signed R. Barluttan  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:50 pm Day: 14 Month: FEB. Year: 1983

ACTUAL PLUGGING REPORT plugged as ordered. Cementing  
by Allied. Max. pump pressure 700#, shut  
in pressure 100#.

Remarks: 5 1/2" O.D. @ 4539' w/ 150 sq 50/50 Pozmix  
Plugback TD @ 4557 1/2

RECEIVED  
STATE CORPORATION COMMISSION  
2-17-83  
FEB 17 1983  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as hereinafter stated and that I (did / ~~did not~~) observe this plugging.

INVOICED

Signed R. Barluttan  
(TECHNICIAN)

DATE MAR 24 1983  
IV. NO. 3679-6

FORM CP-2/3  
Rev. 9-82