

052122

4-7

API NUMBER 15- Spud date 9/23/45

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS. 67202

C NW NW, SEC. 26, T 16 S, R 25 W/E

15-135-00478-00-00

4620 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5088

Lease Name Drake Well # 1

Operator: John Jay Darrah Jr.

County Ness 147.81

Name & Address: 225 N. Market, Ste. 300

Well Total Depth 4548 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4 feet 301

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525-0231

Company to plug at: Hour: 4:30 p.m. Day: 7 Month: 4 Year: 19 97

Plugging proposal received from Kent Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

work: 5 1/2" at 4548' w/130 sx cement. Open hole, 4 1/2" liner 4448-1537'

1st plug run tubing to 4500' and spot 30 sx cement and hulls,

2nd plug pull to 1900' and circulate cement to surface.

RECEIVED  
KANSAS CORPORATION  
APR 9 1997  
14-9-97

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 6 p.m. Day: 7 Month: 4 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug ran tubing to 2025' and pumped 200 lbs. hulls and 205 sx cement,

2nd plug pulled tubing and topped off with 25 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1537' of 4 1/2" liner.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
(XXXX/ Bld. No.) observe this plugging.

DATE APR 09 1997

INV. NO. 47896

Signed Richard W. Lacey (TECHNICIAN)