

1 030506

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,911-00-00

SW NW SW, SEC. 19, T 16 S, R 25 (W) X

1650 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9067

Lease Name Horacek 'B' Well # 1

Operator: DaMar Resources, Inc.

County Ness 159.18

Name & Address P. O. Box 70

Well Total Depth 4548 Mississippi feet

Hays, KS 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 299'

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Williamson Drilling License Number 4087

Address 5501 Navajo, Great Bend, KS 67530

Company to plug at: Hour: 12:00 am Day: 5 Month: September Year: 19 85

Plugging proposal received from Terry Williamson

(company name) Williamson Drilling (phone) 316-793-8229

Elevation 2589'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2015'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 50' below the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement - fill water well with 10 sx cement  
Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:35 am Day: 5 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2015' with 50 sx cement, 2nd plug at 1524' with

80 sx cement and 1 sack cellaflock, 3rd plug at 1155' with 40 sx cement, 4th plug

at 314' with 20 sx cement, 5th & 16th plugs - solid bridge - hulls - plug at 40' -- cement

to surface with 10 sx cement, 7th plug to circulate rat hole with 10 sx cement.

Filled water well with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
9-6-85  
SEP 6 1985

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form)  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE SEP 10 1985

Signed Steve Durrant (TECHNICIAN)

INV. NO. 10005