

To: 1 070943
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-6
API NUMBER 15- 135-21,329-00-00 43

S/2 SE NE, SEC. 20, T. 16 S, R. 25 W/4E
2970 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238
Operator: Petroleum, Inc.
Name & Address: 301 N. Main, Suite 900
Wichita, KS 67202

Lease Name Michaelis "B" Well # 5
County Ness 147.77
Well Total Depth 4547 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address P.O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 6 Month: 5 Year: 19 91

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 4522' w/100 sx cement, Open hole 4522-47'
1st plug sand back to 4470' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 50 sx cement and 10 sx gel at 2000',
3rd plug at 1100' with 80 sx cement, 4th plug at 350' with 50 sx cement,
5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:40 p.m. Day: 6 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4470' and dumped 5 sx cement on top of sand through bailer,
2nd plug pulled casing to 2000', pumped 10 sx gel and 50 sx cement and stuck casing,
3rd plug shot casing at 1100' and pumped 80 sx cement,
4th plug pulled to 350' and pumped 50 sx cement,
5th plug topped off with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2539' of 5 1/2" casing.
(if additional descriptive information is necessary, use BACK of this form.)

INVOICED
DATE 5-24-91
INV. NO. 31895

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1991
CONSERVATION DIVISION
Wichita, Kansas

Signed Dan Johnson (TECHNICIAN)