

1051963

9-6

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-101-21,710-00-00
150' S of
W/2 SW SW, SEC. 31, T. 18 S, R. 27 W/E

510 feet from S section line
330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Operator: Ritchie Exploration, Inc.

Name & Address: 125 N. Market, Ste. 1000

Wichita, KS 67202

Lease Name Suchy Well # 1

County Lane 150.80

Well Total Depth 4640 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 207

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address: P.O. Box 48848, Wichita, KS 67201-8848

Company to plug at: Hour: 8:05 p.m. Day: 6 Month: 9 Year: 19 95

Plugging proposal received from Judy

(company name) White & Ellis Drilling, Inc. (phone) 316-263-1102

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2079-90'

1st plug at 2090' with 50 sx cement, 2nd plug at 1060' with 80 sx cement,

3rd plug at 500' with 40 sx cement, 4th plug at 230' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:15 p.m. Day: 6 Month: 9 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug at 2090' with 50 sx cement,

2nd plug at 1060' with 80 sx cement,

3rd plug at 500' with 40 sx cement,

4th plug at 230' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (I checked and did not observe this plugging.)

DATE 9-25-95

Signed Richard W Lacey (TECHNICIAN)

INV. NO. 43597

RECEIVED STATE CORPORATION COMMISSION SEP 08 1995 09-08-1995

FOR KCC USE:

EFFECTIVE DATE: 8-26-95

DISTRICT # 1

SSAT Yes X No

State of Kansas

NOTICE OF INTENTION TO DRILL

101-21,710-00-00

FORM C-1 7/9

FORM MUST BE TYPE

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date Aug 15 95 month day year

Spot 150' S of W/2 SW SW Sec 31 Twp 18 S Rg 27W East West

OPERATOR: License # 4767 Name: Ritchie Exploration, Inc. Address: 125 N. Market, Suite 1000 City/State/Zip: Wichita, KS 67202 Contact Person: Rocky Milford Phone: (316) 267-4375

510 feet from South/North line of Section 330 feet from East/West line of Section IS SECTION X REGULAR IRREGULAR (NOTE: Locate well on the Section Plat on Reverse Side) County: Lane

CONTRACTOR: License #: 5420 Name: White & Ellis

Lease Name: Suchy Well #: 1 Field Name: Seifried SE Is this a Prorated/Spaced Field? yes X no Target Formation(s): L/KC

Well Drilled For: Well Class: Type Equipment: X Oil ... Enh Rec ... Infield ... X Mud Rotary ... Gas ... Storage ... X Pool Ext. ... Air Rotary ... OUVVO ... Disposal ... Wildcat ... Cable ... Seismic: ... # of Holes ... Other ... Other ... If OUVVO: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth

Nearest lease or unit boundary: 330 Ground Surface Elevation: 2725 feet MSL Water well within one-quarter mile: yes X no Public water supply well within one mile: yes X no Depth to bottom of fresh water: 180 Depth to bottom of usable water: 1190 1040' Surface Pipe by Alternates: 1 X 2 Length of Surface Pipe Planned to be set: 200 Length of Conductor pipe required: none Projected Total Depth: 4650 Formation at Total Depth: Miss Water Source for Drilling Operations: well farm pond X other

Directional, Deviated or Horizontal wellbores? yes X no If yes, true vertical depth: Bottom Hole Location:

DNR Permit #: Will Cores Be Taken? yes X no If yes, proposed zone:

Exp. 2/21/96

AFFIDAVIT

RECEIVED STATE CORPORATION COMMISSION 200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well shall be in accordance with the provisions of K.S.A. 201, et. seq.

SEP 08 1995 09-08-1995

CONSERVATION COMMISSION

Pusher Judy SPUD DATE 8-29-95 INIT. SP LENGTH SURFACE PLANNED 200' of 8 5/8" RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLE AHEAD? Y N SIZE HOLE SURFACE PIPE 8 5/8" 20' CONDUCTOR ANHYDRITE T- 2099 B- 2090 ELEVATION TD 4640 FORMATION RAN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ 2090 Ft. W/ 50 SX 1/2 Base Anhy. @ 1060 Ft. W/ 80 SX 1/2, 1/2 Plug @ 500 Ft. W/ 40 SX Bottom Surface @ 230 Ft. W/ 40 SX 40' Plug @ 40 Ft. W/ 10 SX RATHOLE CIRC/W 15 SX MOUSE HOLE W/ SX WATER WELL SX (Irr. Well) Pond Hauling TECHNICIAN R. L DATE 9-1-95 TYPE OF CEMENT 60/40 6% gel 1/4" DATE 9-6-95 STARTING TIME 8:05 (AM/PM) DATE 9-6-95 COMPLETION TIME 10:15 (AM/PM) DATE 9-6-95 CEMENT COMPANY Allward