

To: 1 080131 6-18
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 101-20,022 -00-00
App. NE SW SEC. 22, T 18 S, R 27 ~~XX~~
2010 feet from S section line
3420 feet from E section line
Lease Name Page Well # 1
County Lane 151.32
Well Total Depth 4656 feet
Conductor Pipe: Size feet
Surface Casing: Size 9 5/8 feet 304

TECHNICIAN'S PLUGGING REPORT

Operator License / 30083
Operator: GABS Oil Company
Name & Address 1005 S. School
Ness City, KS 67560

Abandoned Oil Well Gas Well Input Well SWD Well O&A
Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number
Address Ness City, KS 67560

Company to plug at: Hour: 8:45 a.m. Day: 18 Month: 6 Year: 19 97
Plugging proposal received from Brian Gabel
(company name) GABS Oil Company (phone) 913-798-3122

Work: 5 1/2" at 4445.72', PBTD 4415', Perfs at 4274-80', DV @ 2033', cement circulated
1st plug pump 25 sx cement on bottom, 2nd plug at 2060' with 25 sx cement,
3rd plug at 1200' with 25 sx cement, 4th plug at 600' with 25 sx cement,
5th plug at 330' with 25 sx cement, 6th plug at 40' with 5 sx cement.
Gel between all plugs.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12 P.m. Day: 18 Month: 6 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug Plains ran tubing to 4180', Allied pumped 60 sx cement,
2nd plug pulled 68 joints to 2050' and circulated cement with 180 sx cement and 100 lbs.
hulls,
3rd plug pulled tubing and topped off with 20 sx cement. 06-24-1997
Cement down 10' between 9 5/8" X 5 1/2".

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(if additional description is necessary, use BACK of this report.)

(and, if necessary, observe this plugging.)

DATE JUN 25 1997

Signed Kevin D. Shute
(TECHNICIAN)

INV. NO. 48409

6-18 AUG 21 1997

RECEIVED
KANSAS CORP. COM.
1997 JUN 21 P. 12:25 PM