

1030667

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C NW NW SE, SEC. 22, T 18 S, R 27
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,269-00-00
2310 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9310

Lease Name Kuehn B Well # 1

Operator: Bentley Oil & Gas Company
Name & Address: P. O. Box 5012
Wichita Falls, TX 76307

County Lane 150.80
Well Total Depth 4640 Mississippi feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 918

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor DaMac Drilling, Inc. License Number 6333

Address P. O. Box 1164, Great Bend, KS 67530

Company to plug at: Hour: 8:00 pm Day: 28 Month: February Year: 19 86

Plugging proposal received from Blaise Clay

(company name) DaMac (phone) 316-792-1353

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2633
Elevation 2633

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 30' below the base of the surface pipe with 40 sx cement

3rd plug solid bridge
hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 10:00 pm Day: 28 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2050' with 50 sx cement, 2nd plug at 1350' with 50 sx
cement, 3rd plug at 930' with 40 sx cement, 4th & 5th plugs - solid bridge- hulls - plug
at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15
sx cement, 6th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(if additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

MAR 4 1986
03-04-1986
CONSERVATION DIVISION
Wichita, Kansas

INVOICED (not) observe this plugging.
MAR 04 1986

Signed Steve Durrant
(TECHNICIAN)

DATE

INV. NO. 12840

2-28

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

COLLECTION
1-29-86

Starting Date: 2/15/86
month day year

API Number 15- 101-21,269-00-00

OPERATOR: License # 9310 exp 8701

* C NW NW SE Sec 22 Twp 18 S Rge 27
(location) East West

Name Bentley Oil & Gas Company

Address P.O. Box 5012

City/State/Zip Wichita Falls, TX 76307

Contact Person Gene E. Thompson

Phone 817/723-0897

CONTRACTOR: License # 6333

Name DaMac Drilling Inc.

City/State Box 1164 Great Bend, KS 67530

Well Drilled For: Well Class: Type Equipment:

X Oil Swd Infield X Mud Rotary

X Gas Inj Pool Ext. Air Rotary

OWWO Expl Wildcat Cable

If OWWO: old well info as follows:

Operator

Well Name

Comp Date Old Total Depth

Projected Total Depth 4700 feet

Projected Formation @ TD Mississippi

Expected Producing Formations Hertha, Cherokee, Ft Scott

* ...2310! Ft North from Southeast Corner of Section

* ...2310! Ft West from Southeast Corner of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330! feet

County Lane

Lease Name Kuehn, B. Well# 1

Domestic well within 330 feet: yes no

Municipal well within one mile: yes no

Depth to Bottom of fresh water 86! feet

Lowest usable water formation Dakota Formation

Depth to Bottom of usable water 900! feet

Surface pipe by Alternate: 1 2

Surface pipe to be set 925! feet

Conductor pipe if any required feet

Ground surface elevation 2633 feet MSI

This Authorization Expires 6-19-86

Approved By Gene E. Thompson 12-19-85

* Wxs. C.W.S.E 1980 FEL 1980 FEL

Title Geologist

Form C-1 4/84

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 1/22/86 Signature of Operator or Agent

Gene E. Thompson

Gene E. Thompson Title Geologist

2-17-86 Set 919

PUSHER *Blaine Clay*

TD *4640* FORMATION *Miss*

SURFACE PIPE *852 @ 918*

ANHYDRITE *1010* ELEVATION *2633*

STARTING TIME & DATE *2-15-86*

COMPLETION TIME & DATE *10:00pm*

1st PLUG @ *2050* FT. W/ *50* SX

2nd PLUG @ *1350* FT. W/ *50* SX

3rd PLUG @ *930* FT. W/ *40* SX

4th PLUG @ *40* FT. W/ *10 w/SB* SX

RAT HOLE CIRCULATED *15* SX

MOUSE HOLE CIRCULATED *10* SX

WATER WELL PLUGGED *W* SX

CEMENT COMPANY *Hall*

TECHNICIAN *Paul*

St. B. Hwy. w/50sx.

2600 B. Hwy. + 20 w/40sx.

40 B. Hwy. + 10 w/10sx.

Gene E. Thompson

MAR 4 1986
03-04-1091
Wichita, Kansas