

1 070725

9-20

92

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,220-00-00

NE SE NW, SEC. 17, T 18 S, R 27 W/E

3630 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Stanley "A" Well # 1

Operator: Chief Drilling Company, Inc.
Name & Address 224 East Douglas, Suite 350
Wichita, KS 67202

County Lane 151.45

Well Total Depth 4660 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Company License Number 5883

Address 224 East Douglas, Suite 350, Wichita, KS 67202

Company to plug at: Hour: 1:15 p.m. Day: 20 Month: 9 Year: 19 89

Plugging proposal received from Gary Lindenmuth

(company name) Chief Drilling Company, Inc. (phone) 316-262-3791

were: 4 1/2" at 4658' PBSD 4636' Perfs at 4581-98' Port collar at 2110' w/450 sx cement

1st plug pump 500 lbs. hulls and 120 sx ATL cement in 4 1/2",

2nd plug pump 50 sx ATL cement in backside if it will take.

RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1989
09-26-1989
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:15 p.m. Day: 20 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 500 lbs. hulls and 125 sx ATL cement down 4 1/2",

Maximum pressure 1500 psi and shut in 1500 psi.

2nd plug pumped 8 sx cement down backside, pressured to 800 psi.

Remarks: Used ATL cement by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-28-89

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 25964