

5-15

1 070809

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,307-00-00

NE NE SW, SEC. 17, T 18 S, R 27 W/E
2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5886
Operator: Chief Drilling Company, Inc.
Name & Address: 224 East Douglas, #530
Wichita, KS 67202

Lease Name Stanley "C" Well # 1
County Lane 150.80
Well Total Depth 4640 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well X Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Company License Number 5883
Address 224 East Douglas, #530, Wichita, KS 67202

Company to plug at: Hour: 3:30 p.m. Day: 15 Month: 5 Year: 19 90

Plugging proposal received from Douglas W. Thimesch

(company name) Chief Drilling Company, Inc. (phone) 316-262-3791

were: 4 1/2" at 4554' PBDT 4554' Perfs at 4434-4460' DVE

1st plug pump 2 sx hulls and fill with light cement. 200 sx ATL down 8 7/8 x 4 1/2"

2nd plug pump 100 sx cement down annulus. backside Temp survey to 200'

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4:30 p.m. Day: 15 Month: 5 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 400 lbs. hulls and 170 sx cement down 4 1/2",

Maximum pressure 1000psi and shut in 500 psi.

Backside would not take at 750#.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.
(if additional description is necessary, use BACK of this form.)

INVOLVED

observed this plugging.

DATE 5-30-90 MAY 22 1990 05-25-1990

Signed Dan Goolrow (TECHNICIAN)

WICH. NO. 28286 CONSERVATION DIVISION
Wichita, Kansas