

To: 1052033
STATE CORPORATION COMMISSION

API NUMBER 15- 101-21,718-00-00

Wichita State Office Bldg. PLUGGING SECTION App. SE NE SW, SEC. 16, T 18 S, R 27 ~~W~~
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

4-20

Operator License # 4767

1560 feet from S section line
2268 feet from ~~W~~ section line
Lease Name Lena Speer Well # 1

Operator: Ritchie Exploration, Inc.
Name: 125 N. Market, Ste. 1000
Address: Wichita, KS 67202

County Lane 150.24
Well Total Depth 4623 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 231

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling License Number 5420

Address P.O. Box 48848, Wichita, KS 67201-8848

Company to plug at: Hour: 7:45 a.m. Day: 20 Month: 4 Year: 19 96

Plugging proposal received from Don Demel

(company name) White & Ellis Drilling (phone) 316-263-1102

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2071-2100'
1st plug at 2100' with 50 sx cement, 2nd plug at 1000' with 80 sx cement,
3rd plug at 500' with 40 sx cement, 4th plug at 260' with 40 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:45 a.m. Day: 20 Month: 4 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement,
2nd plug at 1000' with 80 sx cement,
3rd plug at 500' with 40 sx cement,
4th plug at 260' with 40 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION
APR 30 1996
04-30-1996
CONSERVATION DIVISION
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

(If you did not observe this plugging.)

Signed Richard M. Lacey
(TECHNICIAN)

INVOICED

DATE 5-1-96
INV. NO. 45505

EFFECTIVE DATE: 4-9-96

State of Kansas

101-21,718-00-00

FORM MUST BE TYPED

DISTRICT #

NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED

SGA7... Yes... No

Must be approved by the K.C.C. five (5) days prior to commencing well

ALL BLANKS MUST BE FILLED

Expected Spud Date April 10 96

Spot SE NE SW Sec 16 Twp 18 S Rg 27W East West

OPERATOR: License # 4767
Name: Ritchie Exploration, Inc.
Address: 125 N. Market, Suite 1000
City/State/Zip: Wichita, KS 67202
Contact Person: Lisa Thimmesch
Phone: (316) 267-4375

1650 1560 feet from South/North line of Section
12970 2263 feet from East/West line of Section
IS SECTION X REGULAR IRREGULAR?

CONTRACTOR: License #: 5420
Name: White & Ellis Drilling

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Lane
Lease Name: Lena Speer Well #: 1
Field Name: Wildcat

Well Drilled For: Well Class: Type Equipment:
Oil Enh Rec Infield Mud Rotary
Gas Storage Pool Ext. Air Rotary
OWWO Disposal Wildcat Cable
Seismic: # of Holes Other
Other
If OWWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): L/KC
Nearest lease or unit boundary: 330 362
Ground Surface Elevation: 2694 feet MSL
Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no
Depth to bottom of fresh water: 200
Depth to bottom of usable water: 1000
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 200 370
Length of Conductor pipe required: none
Projected Total Depth: 4580
Formation at Total Depth: Miss
Water Source for Drilling Operations: well farm pond X other

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:
Exp. 10/4/96

DWR Permit #:
Will Cores Be Taken? CORPORATION COMMISSION X no
If yes, proposed zone:

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

RECEIVED APR 20 1996 II Req. 04-30-1996 CONSERVATION DIVISION WICHITA, KS

Pusher Andy Ann Demel
SPUD DATE 4-12-96 INIT. ydw
LENGTH SURFACE PLANNED 2207

RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 5 3/8 @ 231 CONDUCTOR
ANHYDRITE T- 2071 B- 2100 ELEVATION

TD 4623 FORMATION 11/24
RAN PIPE @ DV TOOL ALT II DONE SX Y N
Arbuckle Plug @ Ft. W/ SX
Plug./Council @ Ft. W/ SX
Anhydrite Base @ 2100 Ft. W/ 50 SX
1/2 Base Anyh. @ 1000 Ft. W/ 80 SX
1/2, 1/2 Plug @ 500 Ft. W/ 40 SX
Bottom Surface @ 260 Ft. W/ 40 SX
40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well) Pond Hauling
TECHNICIAN R. L. DATE 4-19-96
TYPE OF CEMENT 60/40 per 6 1/2 bags 1/4 Floccul
STARTING TIME 2:40 (AM/PM) DATE 4/20/96
COMPLETION TIME 4:45 (AM/PM) DATE 4/20/96
CEMENT COMPANY Alltel 1796