

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-21463-00-00  
Spot: CN2NWNE Sec/Twnshp/Rge: 16-18S-27W  
4950 feet from S Section Line, 1980 feet from E Section Line  
Lease/Unit Name: MUCHOW Well Number: 1  
County: LANE Total Vertical Depth: 4664 feet

Operator License No.: 31627  
Op Name: WHITETAIL CRUDE, INC  
Address: 201 W ASH PO BOX 544  
NESS, KS 67560

Conductor Pipe: Size feet: \$151.58  
Surface Casing: Size 8.625 feet: 233 WITH 140 SX CMT  
Production: Size 5.5 feet: 4662 WITH 115 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/26/2001 9:15 AM

Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: TED Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: SPOT 60 SX CMT & 500# HULLS AT 4500' THROUGH TUBING. PULL TUBING TO 2100' & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE OF 5 1/2" WITH 15 SX CMT & PRESSURE UP TO 500#.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 01/26/2001 12:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4605'. PERFS AT 4561-71, 4613-19'. CIBP @ 4605'. PERFS AT 4522-4527'. ALT II HAD BEEN COMPLETED. PUMP 60 SX CMT AND 400# HULLS @ 4500' THROUGH TUBING. PULL TUBING TO 2100' AND CIRCULATE CMT. USED 160 SX CMT TO CIRCULATE. PULLED TUBING AND TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE AND PUMPED 15 SX CMT. PRESSURED TO 500# AND HELD.

**INVOICED**

DATE 03-08-2004

INV. NO. 2001061453

RECEIVED  
STATE CORPORATION COMMISSION

JAN 31 2001

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

01-31-2001  
CONSERVATION DIVISIO..

Plugged through: TBG

District: 01

Signed

Michael J. Maier  
(TECHNICIAN)

JAN 29 2001

Form CP-2/3

MP

RAY