

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR A. L. Abercrombie, Inc.

ADDRESS Rt. #1 Box 56 Great Bend, Ks. 67530

PHONE#(316) 793-8186 OPERATORS LICENSE NO. 5393

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-4-94 (date)

by David P. Williams Prod. Supervisor (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation Lans KC/Marm. Depth to Top 3769 Bottom 4210 T.D. 4460

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lans KC	Oil - water	4039	43	8 5/8	256	None
		4134	36			
Marmaton	Oil - water	4174	77	4 1/2	4458	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Mix & displace down 4 1/2 csg.-300# Hulls; 230 sacks 60/40 Poz 8% Gel to max press 700# -Shut in
Mix 15 sacks 60/40 Poz 8% Gel & displace down 8 5/8" annulus with 500# standing. Job complete
at 12:05 PM 12-20-94. Job okayed Via telephone to Duane Rankin.

Name of Plugging Contractor A. L. Abercrombie, Inc. License No. 5393

Address Rt. #1, Box 56 Great Bend, Ks. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A. L. Abercrombie, Inc.


STATE OF Kansas COUNTY OF Barton, ss.

E. L. Abercrombie

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) E. L. Abercrombie

(Address) Rt. #1, Box 56 Great Bend, Ks. 67530



SUBSCRIBED AND SWORN TO before me this 23rd day of December 19 94

Susan M. Evers
 Notary Public

My Commission Expires: 7-29-96

USE ONLY ONE SIDE OF EACH FORM

RECEIVED 19 94
 STATE CORPORATION COMMISSION
 DEC 28 1994
 12-28-1994
 CONSERVATION Form 100-4
 Revised 05-88
 WICHITA, KANSAS