

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-101-21,496-00-00

LEASE NAME Jasper

WELL NUMBER 1-6

2970 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 6 TWP. 16SRGE. 29 ~~xx~~ (W)

COUNTY Lane

Date Well Completed 2-27-89

Plugging Commenced 2-27-89

Plugging Completed 2-27-89

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR White & Ellis Drilling, Inc.

ADDRESS 401 E. Douglas - Suite 500, Wichita, KS 67202

PHONE# (316) 263-1102 OPERATORS LICENSE NO. 5420

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? YES

Which KCC Office did you notify? District 6

Is ACO-1 filed? NO If not, is well log attached? NO

Producing Formation ACO-1 and well log will be filed by Operator.

Depth to Top N/A Bottom T.D. 4450'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled
				8 5/8"	357'	None

RECEIVED
 STATE CORPORATION COMMISSION
 03-10-1989
 MAR 10 1989
 CONSERVATION DIVISION
 WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the cement fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet set each set.

Spotted 50 sx. cement @ 2080' thru drill pipe.

Spotted 80 sx. cement @ 1500' thru drill pipe.

Spotted 40 sx. cement @ 360' thru drill pipe.

Spotted 40 sx. cement @ 40' thru drill pipe. Spotted 15 sx. cement in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address 401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Michael L. Considine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Michael L. Considine


(Address) 401 E. Douglas - Suite 500

SUBSCRIBED AND SWORN TO before me this 9th day of March, 19 89

David F. Jamis
 Notary Public

My Commission Expires:





15-101-21496-00-00

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: White & Ellis Drilling, Inc., 401 E. Douglas - Suite 500, Wichita, KS 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500, Wichita, Ks. 67202

Lease Name Jasper Well No. 1-6

Sec. 6 T. 16S R. 29W Spot SW SW NW

County Lane State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 357' with 190 sx. 2% Gel 3% CC

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4450'

Drilling Commenced 2-20-89 Drilling Completed 2-27-89

Formation	From	To	Tops
Cellar	0	7	
Shale	7	1193	
Shale, Sand	1193	2470	
Shale	2470	3900	
Shale, Lime	3900	4105	
Lime	4105	4324	
Shale	4324	4450	

RECEIVED
STATE CORPORATION COMMISSION

MAR 10 1989
03-10-1989
CONSERVATION DIVISION
Wichita, Kansas