

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,546-0000

LEASE NAME Kerkhoff

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

4270 2846 Ft. from S Section Line
4670 4894 Ft. from E Section Line

LEASE OPERATOR South Lake Exploration

SEC. 16 TWP. 16S RGE. 29 ~~KEXXX(W)~~

ADDRESS P. O. Box 926691, South Lake, TX 76092

COUNTY Lane

PHONE# (817) 430-1304 OPERATORS LICENSE NO. 30324

Date Well Completed 04-10-90

Character of Well D&A

Plugging Commenced 04-10-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 04-11-90

The plugging proposal was approved on 04-11-90 (date)

by State Plugger, Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	327'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Circulate heavy mud in hole. 1st plug from 2100' to 1900' w/50 sx. 2nd plug from 1350' to 1030' w/80 sx. 3rd plug from 360' to 200' w/40 sx. 4th plug from 40' to surface w/10 sx. Rathole-15 sx. All cement 60/40 pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: South Lake Exploration


STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 4th day of May, 1990



MAY 07 1990
05-07-1990
CONSERVATION DIVISION
Wichita, Kansas

Sharan J. Branstetter Notary Public

My Commission Expires: 05-18-93