





15-101-21242-00-00

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLER'S WELL LOG

Jennison "B" #1  
NW SE NW Sec. 8-16S-29W  
Lane County, Kansas  
Commenced: 11-12-85  
Completed: 11-22-85  
API #15-101-21,242  
Operator: American Energies Corporation

Depth		Formation	Remarks
From	To		
0	395	Clay	Ran 9 joints (375') new, 23#,
395	640	Sand, Shale	8 5/8" surface casing. Set at 385'
640	664	Clay	with 225 sxs 60/40 poz, 2% gel,
664	1408	Clay, Sand, Shale	3% cc. Plug down at 8:45 p.m. on
1408	2015	Clay, Shale	11-12-85. Cement did circulate.
2015	3265	Lime, Shale	Job by Allied, Ness City, Kansas.
3265	3424	Shale	
3424	3800	Lime, Shale	RTD 4527'
3800	3875	Lime	
3875	4527	Lime, Shale	Plugged well with 200 sxs 60/40
		RTD	poz, 6% gel as follows: 2155-
			50 sxs; 1150'-70 sxs; 420'-50 sxs;
			40'-10 sxs with solid bridge;
			rathole-10 sxs; mousehole-10 sxs.
			Plug down at 7:00 a.m. on 11-22-85.
			Job by Allied, Ness City. State
			plumber was out of the Dodge
			City, Kansas office.

STATE OF KANSAS )  
                    ) ss  
COUNTY OF PRATT )

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

*Arnie Little*  
ARNIE LITTLE, PRESIDENT

*Mary L. Tjaden*  
NOTARY PUBLIC



RECEIVED  
STATE CORPORATION COMMISSION  
DEC 10 1988  
10-04-1988  
CONSERVATION DIVISION  
Wichita, Kansas

My Commission Expires:

3/22/88