

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-101-21,680 00-00

LEASE NAME Eaton

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

330 Ft. from S Section Line

2,970 Ft. from E Section Line

SEC. 13 TWP. 16 RGE. 29 (E) or (W)

LEASE OPERATOR Staab Oil Co.

COUNTY Lane

ADDRESS 1960 280th Avenue, Hays, KS. 67601

Date Well Completed 10-21-94

PHONE# (913) 625-3013 OPERATORS LICENSE NO. 6037

Plugging Commenced 10-21-94

Character of Well D & A

Plugging Completed 10-21-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-21-94 (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? NO If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 4,560'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	236'	Cmtd. w/165 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.  
Spot 50 sax cement @2,175' thru drill pipe. Push bridge plug to 1,250', spot 80 sax cement on plug thru drill pipe. Push bridge plug to 600', spot 40 sax cement on plug thru drill pipe. Push plug to 260', spot 40 sax cement on plug thru drill pipe. Push bridge plug to 40', -dump 10 sax on plug. Dump 15 sax cement down rathole and 10 sax cement down mouse hole.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 160

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Staab Oil Co.

STATE OF KANSAS COUNTY OF RUSSELL, ss. 11-01-1994

M.L. Ratts Contractor (Employee of ~~Operator~~) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) Shields Bldg., Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 26th day of October 1994

My Commission Expires:

RUTH PHILLIPS  
State of Kansas  
My Appt. Exp. 5-26-95

Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 03 1994  
EATON DIVISION  
WICHITA, KANSAS  
Form CP-4  
Revised 05-88



15-101-21680-00-00


Shields

Russell, Kansas

WELL LOG

Operator: Staab Oil Co.  
 Well: Eaton #1  
 Commenced: October 11, 1994  
 Completed: October 21, 1994  
 Contractor: Shields Drilling Co.

Well Description: SE SE SW  
 Sec. 13-16S-29W  
 Lane County, KS.



CASING RECORD

Size	Run	Pulled
8 5/8"	236'	Cmtd. w/165 sax

Elevation: 2,755' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations .....

Sand & shale	2,145'
Anhydrite	2,174'
Shale & sand	2,250'
Shale	3,107'
Shale & lime streaks	3,205'
Lime & shale	3,762'
Lime	4,560' RTD

Notes

11-01-1994

RECEIVED  
STATE CORPORATION COMMISSION

NOV 01 1994

10/11