

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-101-21,541-00-00

LEASE NAME Dickey "I" 0

WELL NUMBER #20

4290' Ft. from S Section Line

2000' Ft. from E Section Line

SEC. 31 TWP. 16S RGE. 29 ~~(W)~~ or (W)

COUNTY LANE

Date Well Completed 2-13-90

Plugging Commenced 2-13-90 3:00 AM

Plugging Completed 2-13-90 5:30 AM

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Slawson Exploration Company, Inc.

ADDRESS 104 S. Broadway, Wichita, Kansas 67202

PHONE#(316) 263-3201 OPERATORS LICENSE NO. 3988

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 13, 1990 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4580'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	307'	8 5/8"	307'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

1st plug @ 2260' W/50 sx. 60/40 Pozmix, 6% Gel, 2nd plug @ 1400' W/80 sx., 3rd plug @ 350' W/50sx

4th plug @ 40' W/10 sx., 15 sx. in rathole--Total 205 sx. 60/40 Pozmix, 6% Gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company, Inc. License No. _____

Address Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Slawson Exploration Company, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Greg Davidson (Employee of Operator) or (~~Operator~~) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, I help me God.

(Signature) Greg Davidson

Greg Davidson

(Address) R.R. 1 Box 183 B Great Bend, Ks.

67530

AND SWORN TO before me this 16th day of February, 1990

Bessie M. DeWerff
 Notary Public

Bessie M. DeWerff

My Commission Expires: 5-20-93



RECEIVED
 CORPORATION DIVISION
 FEB 17 1990
 04-27-1990
 CORPORATION DIVISION
 WICHITA, KANSAS

15-101-21541-00-00

DRILLER'S WELL LOG

Commenced: 2-05-90
Completed: 2-13-90

0---- 307 Surface
307---- 2380 Shale W/sand streaks
2380---- 2865 Lime & Shale
2865---- 4580 Lime
4580 RTD

SLAWSON EXPLORATION COMPANY, INC.
DICKY "I" #2
App. S/2 NW NE Sec. 31-16S-29W
Lane County, Kansas

ELEVATION: 2828' GR 2833' KB

FORMATION DATA: (sample)

Anhydrite	2233 (+600)
B/Anhydrite	2264 (+569)
Wabunsee	3533 (-700)
Heebner	3917 (-1084)
Toronto	3936 (-1103)
LKC	3952 (-1119)
Muncie Creek	4122 (-1289)
Stark	4216 (-1383)
BKC	4296 (-1463)
Marmaton	4328 (-1495)
Pawnee	4407 (-1574)
Myrick Station	4436 (-1603)
Ft. Scott	4456 (-1623)
L/Cherokee	4480 (-1647)
Johnson	4521 (-1688)
Miss.	4549 (-1716)
RTD	4580

CONFIDENTIAL

SURFACE CASING:

8 5/8" set @ 307' W/180 sx. 60/40
Pozmix, 2% GEL, 3% CC


A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss

GREG DAVIDSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson
Greg Davidson

Subscribed and sworn to before me this 16th day of February, 1990.



Bessie M. DeWerff
Notary Public: Bessie M. DeWerff

My Commission expires: 5-20-93