

1 070920

2-26

API NUMBER 15- 101-20,095 - 00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE 'SW SW, SEC. 18, T 17 S, R 27 W/E  
330 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4058

Lease Name Collins Well # 5

Operator: American Warrior, Inc.

County Lane 148.55

Name & Address P.O. Box 399

Well Total Depth 4571 feet

Garden City, KS 67846

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor American Warrior, Inc. License Number 4058

Address P.O. Box 399, Garden City, KS 67846

Company to plug at: Hour: 11:40 a.m. Day: 26 Month: 2 Year: 91

Plugging proposal received from Dean Ives

(company name) American Warrior, Inc. (phone) 913-625-7773

were: 4 1/2" at 4316' w/125 sx cement, PBD 4316', Perfs at 4165-4204'

DV at 2080' w/400 sx cement to 0'

1st plug pump 400 lbs. hulls ahead of 400 lbs. hulls in first part of 95 sx Econolight cement.

2nd plug pump 90 sx cement down 8 5/8".

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:45 p. Day: 26 Month: 2 Year: 91

ACTUAL PLUGGING REPORT 1st plug pumped 400 lbs. hulls ahead of 400 lbs. hulls in first

part of 95 sx Econolight cement. Maximum pressure 1000 psi and shut in 0 psi.

2nd plug pumped 90 sx cement down 8 5/8", cement came to surface.

RECEIVED STATE CORPORATION COMMISSION

MAR - 1 1991

CONSERVATION DIVISION

Remarks: Used Econolight cement by Halliburton. No casing recovery. Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED (If possible, observe this plugging.)

DATE 3-8-91

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 31066

2-26 MAY 03 1991