

1 030141

API NUMBER 15- 101-20,947 -00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW SW SW , SEC. 17 , T 17 S, R 27 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

330 feet from XYS section line
330 feet from W/EX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Lease Name Waterson Trust Well # 'B' 2

Operator: Mull Drilling Company, Inc.

County Lane

Name & Address P. O. Box 2758

Well Total Depth 4700 152.75 feet

Wichita, KS 67201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 389

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Mallard Drilling Co., Inc. License Number 5651

Address 405 Century Plaza Building

Company to plug at: Hour: 4:00 pm Day: 24 Month: March Year: 19 84

Plugging proposal received from Wayne Stout

(company name) Mallard Drilling Co., Inc. (phone) 316-263-8218

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2120' with 50 sx cement 3rd plug at 720' with 50 sx cement

2nd plug at 1020' with 50 sx cement 4th plug at 390' with 40 sx cement

5th plug hulls - plug at 40' -- cement to surface with 10 sx cement

7th plug to circulate rathole with 10 sx cement

8th plug to circulate mousehole with 10 sx cement

Plugging Proposal Received by Steve Dumont (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:25 pm Day: 24 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2120' with 50 sx cement, 2nd plug at 1020' with

50 sx cement, 3rd plug at 720' with 50 sx cement, 4th plug at 390' with 40 sx cement,

5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx

cement, 7th plug to circulate rathole with 10 sx cement, 8th plug to circulate

mousehole with 10 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form)

INVOICED (did not) observe this plugging.

DATE 4-4-84

INV. NO. 1053 3-24

Signed Steve Dumont (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION MAR 29 1984 CONSERVATION DIVISION Wichita, Kansas