

1 120001

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101 20,872-00-00

2310 N SW SW NE, SEC. 30, T 17 S, R 27 W/E  
2310 E FEET FROM ~~W/S~~ SECTION LINE  
AND VCC  
FEET FROM ~~W/E~~ SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5144

LEASE NAME Neeley WELL # 1

OPERATOR: Mull Drilling Company, Inc.  
NAME & P. O. Box 2758  
ADDRESS Wichita, KS 67201

COUNTY Lane

WELL TOTAL DEPTH 4648 151.06 FEET

CONDUCTOR PIPE: SIZE \_\_\_\_\_ FEET \_\_\_\_\_

SURFACE CASING: SIZE 8 5/8 FEET 344

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR Murfin Drilling Company LICENSE NUMBER 6033

ADDRESS 617 Union Center Building, Wichita, KS 67202

COMPANY TO PLUG AT: HOUR: 6:30 pm DAY: 10 MONTH: February YEAR: 19 84

PLUGGING PROPOSAL RECEIVED FROM Alfred Augustine

(COMPANY NAME) Murfin Drilling (PHONE) 913-625-6667

WERE: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 1240' with 70 sx cement

2nd plug at 403' with 50 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

PLUGGING PROPOSAL RECEIVED BY Don C. Uebel  
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL \_\_\_\_\_ PART \_\_\_\_\_ NONE

OPERATIONS COMPLETED: HOUR: 11:00 pm DAY: 10 MONTH: February YEAR: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1240' with 70 sx cement, 2nd plug at 403' with

50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to

surface with 10 sx cement, 5th plug to circulate rathole with 15 sx cement.

REMARKS: Use 60/40 Pozmix with 2% gel and 3% cc. by Halliburton

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 15 1984  
CONSERVATION DIVISION  
Wichita, Kansas

I ~~(XXX)~~ / DID NOT OBSERVE THIS PLUGGING.

SIGNED Don C. Uebel  
(TECHNICIAN) ✓

INVOICED

DATE 2-23-84

INV. NO. 0348

FORM CP-2/3  
REV. 6-83