

To: 1 071052
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-17
API NUMBER 15- 101-20,149-00-00 1248
150' NW of
SE NW NW, SEC. 30, T. 17 S, R. 27 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364
Operator: Beren Corporation
Name & Address P.O. Box 723
Hays, KS 67601

4365 feet from S section line
4365 feet from E section line
Lease Name Harlamert A Well # 1
County Lane
Well Total Depth 4624 150.28 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 355

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Beren Corp. License Number 5364
Address P.O. Box 723, Hays, KS 67601

Company to plug at: Hour: 2:45 p.m. Day: 17 Month: 4 Year: 19 92

Plugging proposal received from Ted Crawford

(company name) Beren Corp. (phone) 913-628-6101

work: 4 1/2" at 4619' w/150 sx cement, PBD 4589', Perfs at 4192-4562', Squeezed hole at 1635'
1st plug pump 500 lbs. hulls and 225 sx cement down 4 1/2", displace with water to 1300', w/129' sx

2nd plug perforate at 1300' and pump 150 sx cement,

3rd plug pump 100 sx cement in backside.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:45 p.m. Day: 17 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 500 lbs. hulls and 225 sx cement down 4 1/2", displaced with water to 1300',

2nd plug perforated at 1300' and pumped 150 sx cement. Maximum pressure 950 psi and shut in 0 psi.

3rd plug pumped 100 sx cement in backside. Maximum pressure 300 psi and shut in 0 psi.

Remarks: Used 60/40 Pozmix 8% gel by B.J. Services. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE MAY 04 1992

INV. NO. 35108

Signed Dan Goodrow
(TECHNICIAN)

STATE CORPORATION COMMISSION
RECEIVED
APR 24 1992
CONSERVATION DIVISION
Wichita, Kansas