

To: 1 090053
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-7

101 P

API NUMBER 19-101-20,837-00-01
SW NW NW, SEC. 29, T. 17 S, R. 27 W/E

4290 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5011

Lease Name Leo Well # 1

Operator: Viking Resources, Inc.
Name & Address 105 S. Broadway, Ste. 1040
Wichita, KS 67202-4224

County Lane Lane 143.29
Well Total Depth 4409 feet

Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 332

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Well Service License Number 6454

Address P.O. Box 384, Ness City, KS 67560

Company to plug at: Hour: 4 p.m. Day: 7 Month: 2 Year: 1991

Plugging proposal received from Terry Richardson

(company name) Viking Resources, Inc. (phone) 913-625-4567

were: 4 1/2" at 4374' w/250'sx cement, Perfs at 4209-12, 4272-74'
1st plug set CIBP at 4000',

2nd plug pump 10 sx gel and 100 sx cement at 2126', 3rd plug pump 50 sx cement at 960',

4th plug pump 40 sx cement at 360',

5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 8:30 p.m. Day: 7 Month: 2 Year: 1991

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4000' with 2 sx cement on top,

RECEIVED
STATE CORPORATION COMMISSION

2nd plug spot 10 sx gel at 2125' and 100 sx cement,

3rd plug pulled to 960' with 50 sx cement,

FEB 13 1991

4th plug pulled to 360' with 40 sx cement,

CONSERVATION DIVISION
Wichita, Kansas

5th plug pumped 10 sx cement at 40'.

Remarks: Used 60/40 Pozmix 8% gel by Allied. Recovered 2770' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

(did / ~~XXXXXX~~) observe this plugging.

INVOICED

Signed [Signature]
(TECHNICIAN)

DATE 3-5-91

INV. NO. 31013
2-7