

1 090264

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,102 *of-oo*
SE SW SW, SEC. 29, T 17 S, R 27 W/E

330 feet from N/S section line
4600 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9954

Lease Name Harlamert Well # 1 Opal

Operator: L. J. Erskin Oil

County Lane Lane 152.10

Name & Address 116 E. Long

Well Total Depth 4680 feet

Dighton, KS 67839

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A

Other well as hereinafter indicated _____

Plugging Contractor Aldebaran Drilling Company, Inc. License Number 5829

Address Box 18611, Wichita, KS 67207

Company to plug at: Hour: 5:00 pm Day: 19 Month: December Year: 19 84

Plugging proposal received from Bill Cheshire

(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2100' with 50 sx cement

2nd plug at 1590' with 50 sx cement

3rd plug at 480' with 70 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement

10 sx cement

Plugging Proposal Received by R. B. Arbutan
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 7:00 pm Day: 19 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement, 2nd plug at 1590' with 50

sx cement, 3rd plug at 480' with 70 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 02 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

did not observe this plugging.

Signed R. B. Arbutan
(TECHNICIAN)

INVOICED
DATE 1-14-85
INV. NO. 6411