

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,800-00-00

SE, Sec. 28, T 17 S, R 27 W

1980 feet from N/S section line

660 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5063

Lease Name Enex Mumma Well # 1

Operator: Energy Exploration Inc
Name & Address 1002 South Broadway
Wichita, Kansas 67211

County Lane
Well Total Depth 4615 feet \$149.99
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 353

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor H-30 Drilling Inc License Number 5107

Address 251 North Water Wichita, Kansas 67202

Company to plug at: Hour: 2:30 Day: 8 Month: June Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Kendall Zahn

(company name) H-30 Drilling (phone)

were: To use 60/40 Pozmix, 2% gel 3% cc
1st plug @ 2100' w 50sx, 2nd Plug @
1530 w/50sx, 3rd plug @ 420 w/40sx,
4th plug @ 40' w/solid Bridge plug + 10sx
circulate 15sx in rathole Use 60/40 pozmix
2% gel 3% cc

Signed Richard W. Lacy
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:00 pm Day: 8 Month: June Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered in above paragraph
Sun pumped the cement

Remarks: Mr. Bob Tarbutton gave plugging orders

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1983

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacy
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED
DATE 6-16-83
INV. NO. 4592-W