

1060309

API NUMBER 15- 101-21,013 -00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW SE SW, SEC. 27; T 17 S, R 27 W/K  
N SE Corner of  
330 FSL feet from NXX section line  
W SE Corner of  
3630 FEL feet from NXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6732

Lease Name Mumma Well # 1

Operator: Vicorp Energy, Inc.

County Lane

Name & Address 6200 South Syracuse Way, # 125

Well Total Depth 4675 151.94 feet

Denver, CO 80111

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 384

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Blue Goose Drilling Company, Inc. License Number 5104

Address Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 7:00 am Day: 18 Month: August Year: 19 84

Plugging proposal received from Leroy Boren

(company name) Blue Goose (phone) 316-692-5633

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2060' with 50 sx cement

2nd plug at 1330' with 50 sx cement

3rd plug at 430' with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthie (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:45 am Day: 18 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2060' with 50 sx cement, 2nd plug at 1330' with 50 sx

cement, 3rd plug at 430' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15

sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 24 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

DATE 8-29-84

Signed Paul A. Luthie (TECHNICIAN)

INV. NO. 3468

8-18